

“Project Cargo on RoRo-Vessels“

Capt. Marc Sommerfeld

13 December 2016, Webinar

Marine and Cargo Surveyors

Project Cargo on RoRo-Vessels

Agenda

1. Introduction
2. Advantages/ Disadvantages of Project Cargo on RoRo Vessels
3. Planning Requirements
4. Planning & Preparation
5. Loading
6. Cargo Securing
7. Final Calculation & Reporting
8. Summary

Project Cargo on RoRo-Vessels

Introduction



Project Cargo on RoRo-Vessels

Introduction

Definition:

“Project cargo is a term used to broadly describe the national or international transportation of large, heavy, high-value or critical (to the project they are intended for) pieces of equipment. Also commonly referred to as Heavy Lift, this includes shipments made of various components which need disassembly for shipment and reassembly after delivery.”

Project Cargo on RoRo-Vessels

Introduction

“Billions of dollars of project-critical equipment is shipped around the world annually.”

“High levels of risk are associated with these shipments due to the nature of the cargo, transport logistics, and tight timeframes.”

(Source: <http://www.agcs.allianz.com/services/marine/project-cargo/>)

Project Cargo on RoRo-Vessels

Introduction

Various Possibilities of Ocean Transport for Project Cargo:

1. Container Vessel



2. RoRo-Vessel



3. Break Bulk Vessel



Project Cargo on RoRo-Vessels

Advantages / disadvantages for the Freight Forwarder

Advantages	Disadvantages
+ Fast vessels/routes	– Larger quantities are not economical
+ Terminals with inland connection/infrastructure	
+ Reputable shipping lines	
+ Standardised transport methods	
+ Costs for single parts are affordable/calculable	

Project Cargo on RoRo-Vessels

Advantages / disadvantages for the Underwriter

Advantages	Disadvantages
<ul style="list-style-type: none">+ Large companies/shipping lines (terminals) → Claims handling department (worst case) / availability+ Always the same structure → easily plannable	<ul style="list-style-type: none">– Timeframe is not always guaranteed, may in part be even worse than in container shipping, as the other cargo is not standardized, thus, potentially higher survey costs due to wait times– Increased risk due to possible transshipping

Project Cargo on RoRo-Vessels

Advantages / disadvantages for the Manufacturer/Shipper/Cargo Owner


Advantages	Disadvantages
<ul style="list-style-type: none">+ No lifting onto vessel (lifting on roll trailer can be carried out in advance at different location)+ Stowage almost exclusively below deck (protective aspect)+ Cargo length can be close to deck length, if cargo loading via the vessel's ramp(s) is possible+ Various types of special equipment available with different shipping lines+ Weekly departures (almost)+ Costs for single parts are affordable/calculable	<ul style="list-style-type: none">– Not always horizontal transport process (ramp to the vessels)– Maximum width limited (stern ramp)– Length limited by vessel ramp due to the multiple bends in ramps– Height limited (stern ramp/deck height clearance)– Weight distribution/footprint must be taken into account, especially when stowed on roll trailer

Project Cargo on RoRo-Vessels

Planning Requirements: Relevant Regulations

1. CSS-Code (Code of Safe Practice for Cargo Stowage and Securing)


+ Transport-related accelerations



Project Cargo on RoRo-Vessels

Planning Requirements: Relevant Regulations

2. Individual design limits of roll trailers



Project Cargo on RoRo-Vessels

Planning Requirements: Relevant Regulations

3. Specific Provisions by the Shipping Lines

Several shipping lines for example stipulate that for cargo units with a weight exceeding 10,000.00, the attachment points for cargo securing are to be applied to and must be accessible on the cargo itself and not on the packaging (e.g. case).



Project Cargo on RoRo-Vessels

Planning Requirements: Pre-Load Inspection

Why is a pre-load inspection so critical?

- ! Basis for plan
- ! Risk assessment / minimising
- ! Documentation of footprint / load points, dimensions, cargo securing points (possible deviations from the documents)
- ! Discovery of prior damage
- ! Cargo anomalies



Project Cargo on RoRo-Vessels

Planning & Preparation


- Pre-calculations of cargo securing with estimated vessel data/ lashing angles/friction (calculation of the cargo securing on roll trailers and of the roll trailers inside the vessel)
- Stowage / lashing sketches are not generally prepared as the surveyor is in attendance during setting down of the cargo onto the roll trailer. Sketches are required only rarely and for very complicated cases.

Completion of Planning:

Inform all parties of maximum values for loading, cargo securing, stowage particulars and work safety


Project Cargo on RoRo-Vessels

Planning & Preparation



the tipping aspect at the rear end of a RT is even worse, as the axles are not as wide as the forward transom

suggested improvement on RT:



NOVUS XXXXXX	WEISS not specified	
Battermann + Tillery Group	DESCRIPTION Tipping aspects	Scale not to scale
	VIEW FRONT	Date 20161212 sheet 01

Project Cargo on RoRo-Vessels

Loading: Stowage on roll trailer prior to loading

Consider the following:

- Load limits (roll trailer load)
- Point loads
- Timber strength
(maximum bend, maximum pressure)
- The requirements regarding roll trailer limits are generally covered in the course of the pre-load inspection.



Project Cargo on RoRo-Vessels

Loading: Preparation

Immediately prior to loading:

- Request vessel data (ship's particulars, expected GM_{max} & $Speed_{max}$)
- Information for vessel's command
- Submit LOI
(Letter of Indemnity)

Project Cargo on RoRo-Vessels

Loading: Preparation

Immediately prior to loading:

- Inspection of deck
- Clarification of the final stowage position



Project Cargo on RoRo-Vessels

Loading

Evaluation of loading operations:

Documentation of the gear and attachment of cargo



Recording of loading times:

Roll on ramp, final set down at stowage position

Project Cargo on RoRo-Vessels

Load Inspection

Important Points of a Load Inspection

- ! Inspection of cargo securing and weight distribution on the loaded roll trailer.
- ! Consideration of the loading process via a ramp during which the cargo is tilted.
- ! Verification whether additional cargo securing towards the deck is required or determining what additional securing is required (Spindle Jacks, chocking, etc.)



Project Cargo on RoRo-Vessels

Cargo Securing

- Inspection of the “weakest link” (lashing points, lashing materials, locking mechanism/ type of lashing, roll trailer lashing point)
- Evaluation of anti-slip mats / determination of the friction coefficient for later calculation



Project Cargo on RoRo-Vessels

Cargo Securing

- Inspection of the tightness of cargo securing
- Note:
 - Web lashings: edge protectors/ cloth
 - Wire: edge protectors/ hoses/ rubber/ remove bends
 - Chains: consider the pressure on chain links across corners and edges
- Document lashing angles
- Instruct vessel's command regarding daily inspections




Project Cargo on RoRo-Vessels

Final Calculation & Reporting

Final Calculation is to Take into Account:


- Received vessel data
- Actual angles
- Maximum tightness to be achieved in accordance with required safety stipulations of the surveyor and the client



Project Cargo on RoRo-Vessels

Final Calculation & Reporting

Documentation of operations or, if applicable, incidents



Project Cargo on RoRo-Vessels

Summary

“Failure of a shipment to arrive intact can quickly turn a \$10 million cargo loss into a \$100 million Delay in Start-Up (DSU) loss when factors such as re-fabrication, shipping, expenses, lost profits and other operational costs are considered.”

(Source: <http://www.agcs.allianz.com/services/marine/project-cargo/>)



Project cargo requires specific care, expertise and meticulous attention to detail.

Thank you very much for
your kind attention!